

THIS DRAWING IS THE SOLE PROPERTY OF HYT ENGG. CO. PVT. LTD. IT SHOULD NOT BE COPIED, DISTRIBUTED, DISPLAYED, REPRODUCED, TRANSMITTED OR USED FOR ANY COMMERCIAL PURPOSE IN ANY FORM OR FOR ANY REASON WITHOUT WRITTEN PERMISSION OF HYT ENGG. CO. PVT. LTD.

INCOMING ELECTRIC POWER SUPPLY WITH EXCLUSIVE EARTHING POINT VOLTAGE BETWEEN NEUTRAL & EARTH LESS THAN 1.0 VOLTS. ISOLATOR SWITCH - 200 AMP. BY CONSIGNEE ELEC LOAD :- REFER LOAD CALCULATION 127.1001.11 LENGTH OF ELECTRIC SUPPLY CABLE :- 10 Mtr (approx.)

PHONE OR HIGH SPEED INTERNET LINE FOR REMOTE DIAGNOSIS TO BE ARRANGED BY CONSIGNEE

HOLDDOWN DEVICE PLATFORM

COMPRESSED AIR INPUT CONSUMPTION : 1 Cu. m/hr. MIN. PRESSURE : 7 bars

STAFF ROOM 4000 x 3000

DEAD END SIDE

12770 (SHED INSIDE)

SLOPE

THESE RAIL ON BOTH SIDES SHOULD BE STRAIGHT WITHOUT CURVATURE UPTO LENGTH OF 22000 mm AND TRACK LYING MATERIAL TO BE PROVIDED BY CONSIGNEE. RAILS SHOULD BE ALIGNED WITH MACHINE RAIL ON BOTH SIDES.

CHIP TROLLEY TO BE PROVIDED BY CONSIGNEE

CONVEYOR

DETAIL-E (See in Foundation drg.)

SECTION A-A (Turned Thru. 90°)

SECTION X-X (TURNED THRO. 90°)

GENERAL NOTES :-

- 1) ALL DIMNS. ARE IN mm.
- 2) DO NOT SCALE DRAWING
- 3) PLEASE ASK IF ANY DOUBT.
- 4) DIMNS. GIVEN IN BRACKET ARE FOR ONLY REFERENCE, NOT TO BE USED FOR PROCESSING.
- 5) THIRD ANGLE METHOD OF PROJ.

LIST OF NECESSARY FACILITIES / AMENITIES, TOOLS & TACKLES TO BE ARRANGED BY CONSIGNEE

- 1) MACHINE ALONG WITH ITS ACCESSORIES SHOULD BE LOCATED IN COVERED SHED ARRANGED BY CONSIGNEE TO AVOIDED EXPOSURE TO RAIN WATER, SUNLIGHT ETC.
- 2) ADEQUATE LIGHTING AND VENTILATION AT MACHINE INSTALLATION AREA WILL BE ARRANGED BY CONSIGNEE BEFORE STARTING FOUNDATION WORK.
- 3) GROSS WEIGHT OF MACHINE APPROX. 35 T. MAX. WEIGHT OF SINGLE PACKING APPROX. 22T.
- 4) CLEAR SITE WITH APPROACH ROAD OF ADEQUATE CAPACITY TO WITHSTAND WEIGHT OF CRANE AND THE MACHINE COMPONENT TO BE ARRANGED BY CONSIGNEE FROM PLACE OF STORAGE TO MACHINE LOCATION.
- 5) ELECTRICITY, WATER & COMPRESSED AIR WILL BE SUPPLIED FREE OF COST AS AND WHEN REQUIRED WITHIN 5 METERS OF ALOCATED SITE DURING FOUNDATION AND INSTALLATION WORK.
- 6) SAFE KEEPING OF MACHINE CONSIGNMENT UNDER COVERED SHED TILL THE TIME OF INSTALLATION WILL BE ARRANGED BY CONSIGNEE.
- 7) EMBEDDED TRACK RAILS ON BOTH SIDE OF MACHINE PIT SHOULD BE ARRANGED BY CONSIGNEE AS PER AT CLAUSE NO 1.2.16.2 OF SEC-V.
- 8) INCOMING ELECTRICAL POWER SUPPLY WITH ISOLATER SWITCH AS PER DRAWING NO. 127.1001.11 AT THE LOCATION MARKED ON THIS DRAWING SHOULD BE ARRANGED BY CONSIGNEE AS PER AT CLAUSE 1.2.17.1 OF SEC-V.
- 9) BEFORE CONFIRMING CLEAR SITE FOR EXCAVATION, CONSIGNEE SHALL KEEP EXTRA SPACE OF MINIMUM 2 MTR ON EACH SIDE TO SAFEGAURD ALL ADJOINING STRUCTURES LIKE COLUMNS ETC. ALSO UNDERGROUND CABLES OR STRUCTURE (IF ANY) SHALL ALSO BE TAKEN INTO CONSIDERATION BEFORE CONFIRMING CLEAR SITE AS EXCAVATION WORK.
- 10) ADEQUATE SPACE FOR STORAGE OF CONSTRUCTION MATERIAL AND EQUIPMENTS TO BE PROVIDED BY CONSIGNEE.
- 11) PERMISSIONS FOR ROUND THE CLOCK WORKING INCLUDING ON HOLIDAYS, DURING PREPARATION OF FOUNDATION, INSTALLATION AND COMMISSIONING OF MACHINE WILL BE ARRANGED BY CONSIGNEE.
- 12) THERE SHOULD NOT BE WATER POND/DITCH WITHIN 5 MTR. FROM THE EDGE OF MACHINE FOUNDATION TO AVOID LEAKAGE OF WATER IN FOUNDATION.
- 13) CALIBRATED WHEEL DIAMETER MEASURING GAUGE, SURFACE ROUGHNESS MEASURING EQUIPMENT, ROAD GAUGE MEASURING EQUIPMENT IF REQUIRED TO CONSIGNEE FOR VERIFICATION TO BE ARRANGED BY CONSIGNEE.
- 14) GOOD TELEPHONE LINE OR HIGH SPEED BROAD BAND LINE WITH MINIMUM BRAKES OR MOBILE, INTERNATE TELEPHONE (PLUG & PLAY TYPE) SHOULD BE ARRANGED BY CONSIGNEE NEAR CONTROL PANEL.

* DURING WARRANTY PERIOD RAILWAYS SHOULD ARRANGE FOLLOWING *

- 1) THROUGH CLEANING OF MACHINE AT THE END OF EACH SHIFT.
- 2) TO CHECK AND MAINTAIN LUBRICATION OIL LEVEL AS PER MANUALS.
- 3) TO CHECK AND MAINTAIN HYDRAULIC OIL LEVEL IN THE HYDRAULIC POWER PACK.
- 4) HYDRAULIC OIL MUST BE TOPPED UP BY THE OIL GIVEN IN INSTRUCTION MANUAL. IN CASE OF EQUIVALENT OIL, COMPLETE OIL IN SYSTEM SHOULD BE DRAINED.
- 5) MACHINE MUST BE OPERATED & MAINTAINED BY OPERATORS & MILLWRIGHT STAFF TRAINED BY HYT FOR OPERATION & MAINTENANCE OF THIS CNC UNDER FLOOR WHEEL LATHE.
- 6) PROPER ELECTRICAL SUPPLY AND EARTHING AS PER DRG. NO. 127.1001.11 SHOULD BE ENSURED.
- 7) AREA AROUND THE MACHINE SHOULD BE KEPT CLEAN.
- 8) NECESSARY SERVICE TOOLS & SPARE SUPPLIED WITH THE MACHINE SHOULD BE AVAILABLE ON THE MACHINE TO HYT ENGINEERS / TECHNICIANS WHILE ATTENDING THE MACHINE.
- 9) ALL THE OPERATING AND ROUTINE MAINTENANCE INSTRUCTIONS GIVEN IN THE MACHINE MANUALS SHOULD BE FOLLOWED.

IMPORTANT NOTES:-

- 1) THIS DRAWING IS FURNISHED FOR PROVISION OF CLEAR SITE & ELECTRICAL SUPPLY FROM CONSIGNEE SIDE. DUE TO CONTINUOUS IMPROVEMENTS, WE RESERVE OUR RIGHT FOR CHANGE IN DIMENSIONS & LOCATIONS OF MACHINE & ITS EQUIPMENTS WITHIN THE CLEAR SITE PROVIDED BY THE CONSIGNEE.
- 2) FOUNDATION DRAWING WITH RCC DETAILS WILL BE SENT BASED ON ACTUAL SITE CONDITIONS BEFORE STARTING THE FOUNDATION WORK.
- 3) MACHINE WEIGHT :- 25000 Kg (approx.)

ELECTRICAL INCOMING POWER SUPPLY 415 $\pm$ 10% VAC, 50 $\pm$ 3%HZ, 3PH. WITH NEUTRAL WITH EXCLUSIVE, INDEPENDENT EARTHING

R. No.	MOD.	DATE	SIGN	MODIFICATION
21.02.22	NSL			DRG MODIFIED AS PER JOINT NOTE WITH CONSIGNEE
08.03.21	NSL			DRG MODIFIED AS PER CONSIGNEE LETTER
24.11.20	NSL			DRG MODIFIED AS PER CONSIGNEE LETTER

SR. NO.	DESCRIPTION	QTY.
1	APPROCH RAILS (BY CONSIGNEE)	4
2	GUIDE PLATES (BY CONSIGNEE)	4
3	FOUNDATION SLIPPER WITH ANCHORING	4
4	MACHINE RAILS	2
5	SLIDING RAIL ASSEMBLY	1 SET
6	RAILING	1 SET
7	VOLTAGE STABILISER	1
8	ULTRA ISOLATION TRANSFORMER	1
9	CONTROL CONSOLE	1
10	FOUNDATION BOLTS	12
11	CNC UNDER FLOOR WHEEL LATHE	1
12	CHIP TROLLEY BY CONSIGNEE	1
13	LIGHTING	1 SET
14	CONVEYOR A	1
15	CONVEYOR B	1
16	REMOTELY OPERATED RAIL-CUM ROAD VEHICLE SHUNTER	1
17	CONTROL PANEL	1
18	HYDRAULIC POWER PACK	1
19	WATER PUMP & MOTOR FOR SEEPAGE WATER REMOVAL	1
20	CHIP CRUSHER	1

** GENERAL ARRANGEMENT DRAWING WITH OVERALL DIMENSIONS FOR CNC UNDER FLOOR WHEEL LATHE (BG) MODEL NO. YUL-08M COFMOW LOA NO. COFMOW/IR/S/P-2/G-607840 CONSIGNEE :- JABALPUR

PART:- **

DRG.FOR	2020	SIGN	DATE
MATL.-	DRN	NSL	04.02.20
QTY. 01 No.	CHD		
	APPD		
			SCALE : 1:1
			DRG. No.
			127.1001.02-R3